

Cement Stabilized Base & Chipseal ***“County Road 54”***

NRRA Pavement Conference
May 24, 2017


John Brunkhorst, PE - McLeod County Engineer
Dave Rettner, PE - American Engineering Testing Inc.



Topics

1. Background
2. Project Overview
3. Construction Highlights
4. Design Process
5. Construction and Performance Testing
6. Costs
7. Lessons Learned
8. Next Steps

Where is McLeod County?




Located approximately 60 miles west of the Twin Cities

Where is Project?

County Road 54 (CR 54)

~ 6 miles South of Hutchinson, MN



PROJECT LOCATION
Length: ~1 mile

BACKGROUND

County Road 54

- Gravel Road
- Primarily serves rural housing development
- Seasonal agricultural traffic
- ~ 200 ADT
- County Funded (non State Aid route)



BACKGROUND

CR 54 Issues

- ~\$5,000 Annually for Dust Control (CaCl_2)
- Washboards (due to speed/braking)
- Frequent Blading Required
- No Funding for traditional base and surfacing

Goals for CR 54

- Dust Free Road
- Washboard Free
- Stand up to Agricultural Traffic
- Cost Effective



BACKGROUND – Past Efforts

2014 Prime/Seal Project

- CR 54
- Township Housing Development
- Nearby County Park
- *Portions of CR 54 began to break up in fall*



2015 Reclamation & Tiling Project

- CR 54



NOW WHAT?



WAS IT OVER WHEN THE GERMANS BOMBED PEARL HARBOR?

HELL NO!

2016

Cement Stabilized Full Depth Reclamation (CSFDR)

Double Chip Seal & Fog Seal

Project Goal – Find the most cost effective optimal cement content and stabilization depth.



- 4 Test Sections
- Varying Cement Contents
- Varying Stabilization Depths
- Short Section of Single Chip Seal
- 4% Cross Slope



PROJECT OVERVIEW

	Section 1	Section 2	Section 3	Section 4
Cement Content	8 %	7 %	6 %	5 %
Stabilization Depth	10"	10"	8"	8"
Tack Coat	1300'	1300'	1300'	1300'
Double Chip Seal	1300'	1300'	1300'	1200'
Single Chip Seal	-	-	-	100'
Fog Seal	1300'	1300'	1300'	1300'



CONSTRUCTION

Spreading Cement



2016/08/18

CONSTRUCTION

Spreading Cement



CONSTRUCTION

Cement Incorporation



CONSTRUCTION

Cement Incorporation



CONSTRUCTION

Cement Incorporation



CONSTRUCTION

Breakdown Rolling



2016/08/17

CONSTRUCTION

Breakdown Rolling



CONSTRUCTION

Initial Blading



CONSTRUCTION

Finish Rolling



CONSTRUCTION



Finish Rolling & Final Trimming

CONSTRUCTION



Final Trimming

CONSTRUCTION

Finished CSFDR





CONSTRUCTION

Seal Coat – Broom prep



CONSTRUCTION

Tack Coat



CONSTRUCTION

Seal Coat – First Layer



2016/08/22


CONSTRUCTION

Seal Coat – Second Layer



CONSTRUCTION

Seal Coat – Second Layer



CONSTRUCTION

Fog Seal (*sorry no pics* 😊)

8/23/16

DESIGN PROCESS

- **Two mix designs**
 - **One for 8 inch SFDR section, one for 10 inch SFDR section**
 - **Relative proportions of gravel to subgrade were different due to reclamation depths**
 - **8" Section Proctor 127.3 pcf at 9.1% moisture**
 - **10" Section Proctor 122.6 pcf at 10.5% moisture**
 - **Target Unconfined Compressive Strength of 250-300 psi at 14 days**

DESIGN PROCESS

- **Two mix designs**
 - **8" Section**
 - **5% Cement Content at OMC**
 - **272 psi UCS**
 - **10" Section**
 - **7% Cement Content at OMC**
 - **267 psi UCS**

DESIGN PROCESS

- **After lab work was completed the roadways were graveled and graded, so the roadway had more gravel than the mix designs contained.**
- **Likely result was going to be higher strength than the original mix design**


CONSTRUCTION & PERFORMANCE TESTING

- **Field Testing**
 - **Nuclear Gauge for Moisture and Density**
 - **Water was added to soil as necessary to achieve (or approach) optimum moisture content**
 - **Rolling Patterns were performed**
 - **Several Each Day to account for variability in the roadway materials**
 - **Density and moisture was checked during compaction**
 - **Density was typically >98% of rolling pattern density**

CONSTRUCTION & PERFORMANCE TESTING

- **Field Testing**
 - **DCP testing was performed post construction for strength verification**
 - **Target strengths (minimums)**
 - **CBR of 20 in 2 days**
 - **CBR of 50 in 7 days**
 - **Strengths measured greatly exceeded the targets**

CONSTRUCTION & PERFORMANCE TESTING



CONSTRUCTION & PERFORMANCE TESTING

- **Performance Testing**
 - **Ground Penetrating Radar**
 - **Falling Weight Deflectometer**
 - **IRI**
- **Performed October, 2016**

CONSTRUCTION & PERFORMANCE TESTING

- **GPR - Sections were constructed thicker than plan**
 - **10 inch sections**
 - **Section 1 – 14.5 inches**
 - **Section 2 – 14.6 inches**
 - **8 inch Sections**
 - **Section 3 – 11.1 inches**
 - **Section 4 – 10.1 inches**

CONSTRUCTION & PERFORMANCE TESTING

- **FWD Results**
 - **Significant strength increase over non-stabilized roadway – all stabilized sections > 10 tons**
 - **No direct correlation between cement content and strength**


Section	Length	Thickness	Modulus	Load Capacity
	feet	in.	ksi	tons/axle
South Gravel	1300	4.8	16.7	4.8
1	1300	14.5	362.1	20.0
2	1300	14.6	560.9	21.8
3	1300	11.1	438.6	19.0
4	1300	10.1	280.4	10.8
North Gravel	1300	7.6	16.4	5.4

CONSTRUCTION & PERFORMANCE TESTING

- **Ride Quality Results**
 - **IRI of stabilized sections was significantly higher than the unstabilized gravel roadway on both ends of the project**

Section	Length	IRI
	feet	in./mi.
South Gravel	1300	84.8
1	1300	293.2
2	1300	237.4
3	1300	204.4
4	1300	210.9
North Gravel	1300	149.6


CRACK SURVEY - SPRING 2017



CRACK SURVEY - SPRING 2017



CRACK SURVEY - SPRING 2017



CRACK SURVEY - SPRING 2017







1 Year Old



COSTS

CSFDR

- Cement
- Stabilization
- Laydown/Compaction *

Cost/Mile

Cost/SY

\$ 51,300

\$ 3.12

\$ 16,300

\$ 0.99

\$ 15,000

\$ 0.93

CHIP SEAL

- Tack Coat
- 3/8" Seal
- 1/4" Seal
- Fog Seal

\$ 3,100

\$ 0.19

\$ 22,900

\$ 1.40

\$ 20,000

\$ 1.22

\$ 3,300

\$ 0.20

TOTAL


~\$ 132,000

~\$ 8

* County Roller Operators



LESSONS LEARNED



Ride

- Finish longer sections
- Tough to correct after project
- Likely include Ride Spec in Future



LESSONS LEARNED

Subgrade

- Need Good Drainage
- Continue Centerline Tile

Residential Driveways

- Figure out Transition
- Potential Plowing Damage

Future Projects

- No County Operators, One Contract
- Ensure Samples Match Existing Conditions
- 2nd Seal – Year 2 or later



NEXT STEPS

Finish CR 54

- 1 mile 2017
- 2 miles 2018

Continue to Monitor

More Planned

- ~14 Miles in 5-Year Plan

Good Tool in Tool Box for Right Road

- \$140,000/mile vs. Traditional Paving ~\$450,000+





QUESTIONS?



John Brunkhorst, PE
County Engineer

Dave Rettner, PE
President/Principal

McLeod County Hwy Dept.

American Engineering Testing, Inc.

(320) 484-4321
www.co.mcleod.mn.us/highway
john.brunkhorst@co.mcleod.mn.us

(651) 755-5795
www.amengtest.com
drettner@amengtest.com

